

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 119202880001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Quinque Operating Company KCC License #: 5225
(Owner / Company Name) (Operator's)

Address: 908 N.W. 71st St. City: Oklahoma City

State: OK Zip Code: 73116 Contact Phone: (405) 840 - 9876

Lease: Crooked L Well #: 1-20 Sec. 20 Twp. 32 S. R. 28 East West

C - SE/4 - _____ - _____ Spot Location / QQQQ County: Meade

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5" Set at: 1427' Cemented with: _____ Sacks

Production Casing Size: 4 1/2" Set at: 5570' Cemented with: 265 SX Sacks

List (ALL) Perforations and Bridgeplug Sets: 4889'-4892' Sqz off; Curr: 5514-5518'

Elevation: 2525' (G.L. / K.B.) T.D.: 5640' PBTD: 5528' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

See attached plugging procedure.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2008

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

CONSERVATION DIVISION
WICHITA, KS

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Blaine Flaming, Field Supervisor

Quinque Operating Company Phone: (806) 202 - 0046

Address: 908 N.W. 71st St., Oklahoma City, OK 73116 City / State: Oklahoma City, OK

Plugging Contractor: Dollar Oilfield Services KCC License #: 33311

Address: P.O. Box 744, Perryton, TX 79070 Phone: (806) 435 - 3373
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 3/1/08 (approx.)

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/24/2008 Authorized Operator / Agent: Catherine Smith
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

QUINQUE OPERATING COMPANY
908 N.W. 71st ST.
OKLAHOMA CITY, OK 73116
(405) 840-9876 (OFFICE) (405) 840-2011 (FAX)

CROOKED L #1-20
Sec 20-32S 28W
Meade Co., KS

PLUGGING PROCEDURE:

1. MIRU WOCU.
2. TOOH/rods & BH Pump & LD in singles. Install BOP. Rel TAC. TOOH & stand back 2 3/8" tbg.
3. RIH w/4 1/2" CIBP, 2 3/8" tbg. Set plug at 5500'. Circ well & spot 20' cement on CIBP.
4. POOH to 4400' and spot 25 sx cement.
5. POOH to 1500'. Spot 30 sx cement.
6. POOH to 900'. Spot 25 sx cement.
7. POOH to 50'. Circ cement to surface.
8. Remove WH. Place marker over csg noting well name. Place dry hole marker per instructions.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 28 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

QUINQUE OPERATING COMPANY
908 NW 71ST ST
OKLAHOMA CITY, OK 73116-7402

February 12, 2008

Re: CROOKED L #1-20
API 15-119-20288-00-01
20-32S-28W, 1320 FSL 1320 FEL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 10, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888