

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NE NE

SEC. 17 TWP. 8 RGE. 22

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Hickman

Operator Empire Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3527 Feet.

Plugging Contractor Barnes & Sons & Halliburton Co

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 205' circulated with cement - 5 1/2" 3525' with 75 sax cement behind - P. B. to 3450', perforated 3417'.

Filled with sand to 3400', set 4 sax cement with dump bailer - pulled 1390' 5 1/2" to 1000', circulated hole with heavy mud (Gel), displaced 20 sax cement through 5 1/2" at 700', heavy mud to 200', displaced 20 sax cement through 5 1/2" - heavy mud to 35', set rock and 10 sax cement to bottom cellar.

*Edon Kelly*  
District Conservation Agent

Date 12-18-57

PLUGGING  
FILE NO. 17 T 8 R224  
BOOK PAGE 47 LINE 45

RECEIVED  
STATE COMMISSION  
DEC 24 1957  
CONSERVATION DIVISION  
Wichita, Kansas