

DISTRICT CONSERVATION AGENT'S REPORT

*OL*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CE 1/2 NW NE

SEC. 17 TWP. 8 RGE. 22

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Hickman 650 Fourth Nat'l Bldg.

Operator Empire Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3524 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 205' circulated with cement - 5 1/2" 3519' with 75 sax cement

behind - Lane Wells plugs to 3450', perforations 3420'

Filled with sand to 3410', set 4 sax cement with dump bailer, pulled

2620' 5 1/2" to 1000', circulated hole with heavy mud ( 40 sax Gel),

displaced 20 sax cement through 5 1/2" at 700', heavy mud to 190',

displaced 20 sax cement through 5 1/2" at 190', heavy mud to 35', set

rock and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

*Edward Lee*  
District Conservation Agent

Date 12-10-57

*Dec 14, 1957*

PLUGGING  
FILE SEC 17 T 8 R 22  
BOOK PAGE 69 LINE 23