

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 065-21-475 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name L.G. STEPHENSON COMPANY, INC.

Complete Address 7701 - EAST MELLOGG. #670 WICHITA, KANS. 67207

Lease Name QUINT Well-No. #1

Location NW - NW - SE Sec 19 Twp. 8^S Rge. 22^W (East)(West)

County GRAHAM. Total Depth 3675 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor NICHOLAS CASING PULLING (GEO NICHOLAS)

Address BOX 373 GENESEO, KANS. 67444 License No. _____

Operation Completed: Hour: 11:30 AM Day: 20th Month: NOV. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 261 FE SR CUL → 4 1/2" SET @ 3666 FE w/ 125 ST CNT

REFS 3611 FE - 3615 FE → SAND BOTTOM TO 3600 FE AND w/ 1/4 ST CNT.

SHOT. TWICE RECOVERED 2000 FE.

ORDERED 130 ST 50/50 Fozmix 4% GEL. → 3% CA-CL. → 23 ST GEL. → 4 ST HULL'S → 8 5/8" PLUG.

PUMPED IN 8 5/8" WITH PUMP TRUCK.

PUT. IN → 3 ST HULL'S → 15 ST GEL. → 1 ST HULL'S → 70 ST CNT. → 8 ST GEL.

RELEASED PLUG. + 60 ST CNT. MAX. PRESSURE 950 LBS SHUT IN @ 450 LBS

CEMENTED BY FULLER CNT.

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1981

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED
DATE 12-21-81
INV. NO. 8798-W

Signed: Merton Stephenson
Conservation Division Agent