

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

OCT 31 1967
DIVISION

Operator's Full Name Skelly Oil Company,

Complete Address 1860 Lincoln Street, Denver, Colorado.

Lease Name J. M. Moore Well No. X 2

Location NE-SW-NW Sec. 29 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3700'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 5:00PM Day 25 Month 10 Year 1967

The above well was plugged as follows:

235'--8 5/8" Surface pipe, cement circulated with 165 Sx.
3700'--5 1/2" Production casing cemented on bottom with 150 Sx. Stage collar set @ 3115'
with oil circulated to surface. Well plugged back to 3658'. Top perforations from
3506' to 3512'.

Sanded well back to 3490' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with 20 sacks gel from 3510' to 1175' using 5 sacks hulls in initial
gel, followed with 100 Sx. cement from 1175' to 850' then 12 sacks gel from 850' to
250', followed with 20 Sx. cement from 250' to 190' then 3 sacks gel from 190' to 40'
and 10 Sx. cement from 40' to cellar. Maximum pump-in press.-525#. FSIP-250#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/31/67
INV. NO. 6592-W