

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

APR 21 1964  
APR 21, 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas, Incorporated,  
Complete Address: Box # 97, Wakeeney, Kansas.  
Lease Name Dreiling Well No. A-1  
Location NW-NW-SW Sec. 29 Twp. 8 Rge. (E) (W) 22  
County Graham Total Depth 3641  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: HEE 9/23/2005  
Plugging Contractor: Southwest Casing Pulling Company, Incorporated,  
Address: Box # 364, Great Bend, Kansas. License No. 399  
Operation Completed: Hour 4:00PM Day 17 Month 4 Year 1964

The Above well, was plugged as follows:

220'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3640'--5 1/2" casing cemented with 150 Sx. Top perforations from 3252 to 3262'.

Sanded well back to 3242' and set 5 Sx cement with dump bailer.  
Pulled 5 1/2" to 360' and circulated heavy gel mud, ~~xxx~~ (Used 12 Sx. gel)  
and displaced 30 Sx. cement thru 5 1/2". Pulled 5 1/2" to 165' and displaced  
30 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 30' and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. D. Nichols  
Well Plugging Supervisor

Date: 4/21/64  
INV. NO. 8084-W