

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1963
Dec 16, 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas, Inc.,

Complete Address: 780 4TH National Bldg., Wichita, Kansas.

Lease Name Dreiling Well No. A-2

Location NW-NE-SW Sec. 29 Twp. 8 Rgs. (E) (W) 22

County Graham Total Depth 3644

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Inc.,

Address: Box #364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:00AM Day 7 Month 12 Year 1963

The Above well was plugged as follows:

222'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3642'--5 1/2" Production casing, cemented with 100 Sx. Well plugged back to
3509'. Top perforations from 3501' to 3503'.

Pulled 5 1/2" casing to 630' attempted to circulate heavy gel mud, no circu-
lation. (Mixed 6 Sx. gel). Pulled 5 1/2" to 480', attempted to circulate
heavy gel mud, no circulation. (Mixed 6 Sx. gel). Pulled 5 1/2" to 385'
circulated heavy gel mud. (Mixed 9 Sx. gel), and displaced 25 Sx. cement
thru 5 1/2". Pulled 5 1/2" to 210' and displaced 20 Sx cement thru 5 1/2". Pulled
5 1/2", set rock bridge @ 30' and 6 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. P. Nichols*
Well Plugging Supervisor

DATE 12/16/63
INV. NO. 8277-4