

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

NOV 6 1967
NOV 6 1967
CONSERVATION DIVISION

Operator's Full Name Skelly Oil Company.

Complete Address 1860 Lincoln Street, Denver, Colorado.

Lease Name J. M. Moore Well No. 1

Location SW-SW-NW Sec. 29 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3700'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box # 364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 6:00PM Day 28 Month 10 Year 1967

The above well was plugged as follows:

238'--8 5/8" Surface pipe, cement circulated with 180 Sx.
3699'--5 1/2" Production casing cemented on bottom with 150 Sx. Stage collar set @ 3119'
with oil circulated to surface. Bridge plug @ 3683', Top perforations from 3566' to
3570'.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and
squeezed well using 20 sacks gel with 5 sacks hulls in initial gel from 3510' to 1175',
then 100 Sx. cement from 1175' to 850', then 12 sacks gel from 850' to 250', then 20 Sx.
cement from 250' to 190', then 3 sacks gel from 190' to 30' and 10 Sx. cement from 30'
to cellar. Maximum pump-in pressure-400#. Final shut-in pressure-150#.

I hereby certify that the above well was plugged as herein stated.

NOTICED
DATE 11/6/67
INV. NO. 6635-12

Signed: M. L. Nichols
Well Plugging Supervisor