

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -065 -21,082 -00-00 (of this well)

Operator's Full Name Graham-Michaelis Corp.

Complete Address P. O. Box 247, Wichita, Kansas

Lease Name Moore Well No. 1-29

Location 850' FNL & 1320' FEL of NE/4 190's N1/2 NE Sec. 29 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3848'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 A Day 13 Month 12 Year 1978

The above well was plugged as follows:

RTD 3848' 8 5/8 csg set 208' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1978
Dec 18, 1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. J. Massey*
Well Plugging Supervisor

DATE 12-19-78

INV. NO. 8764-W