

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1968
CONSERVATION DIVISION
Wichita, Kansas
11-26-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20175-00-00

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name Frigon Well No. A-1

Location SE-SW-SW Sec. 33 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3976

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. #90

Operation Completed: Hour 1:00PM Day 23 Month 11 Year 1968

The Above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 200 Sx.
3975'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @
3909'.

Sanded well back to 3900' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with initially 15 sacks gel plus 5 sacks hulls in initial gel and
followed with 100 Sx. cement from 1000' to 675' then 10 sacks gel from 675' to 275'
and followed with 20 Sx. cement from 275' to 215' then 5 sacks gel from 215' to 30'
and finally 10 Sx. cement from 30' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/26/68
INV. NO. 8882-W