



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION  
STATE CORPORATION COMMISSION  
SEP 10 1974  
09-10-1974  
CONSERVATION DIVISION  
Wichita, Kansas  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20657-00-00

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Hocker Well No. 1

Location NE-NE-SE Sec. 34 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3880'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.       

Operation Completed: Hour 12:00 M Day 6 Month 9 Year 1974

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement  
thru DP from 1200' to 875'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 9/10/74  
INV. NO. 9862-W