

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21,571-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rms Oil Operations

Complete Address Penobscot, Kansas

Lease Name Law Well No. 1

Location SW-NE-SE Sec. 31 Twp. 8 Rge. 22 (East)(West)

County Shawnee Total Depth 4010

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Circle M Drilg. Pkg 2 627-3511

Address Box 128 Oberlin, Kas. License No. _____

Operation Completed: Hour: 12:00 AM Day: 28 Month: Jan Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" bit @ 278' w/170 sb - 2% gel 3% cc - Circ Cmt. Ordered
130 sb 50/50 proppant 4% gel - 3% cc + 8 5/8" plug
1st plug @ 1050' w/70 sb.
2nd plug @ 270' w/40 sb.
3rd - Solid bridge hulls + plug @ 40'-0' w/10 sb - 10 sb
Rat hole spot w/drill stem - heavy mud between all plugs.

Amount of Surface Casing: 278'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Waiting on call back from Drilling Ventures -
to give orders to plug.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: Dennis L. Hamel
Conservation Division Agent

INVOICED

DATE 3-24-82

INV. NO. 9719-W