

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

DEC 10 1973
12-10-1973
CONSERVATION DIVISION
Wichita, Kansas

15-065-20639-00-00

Operator's Full Name F & M Oil Co., Inc.

Complete Address 603 Union Center, Wichita, Kansas

Lease Name Hull Well No. 1

Location NW NW SE Sec. 32 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor John O. Farmer

Address Wichita, Kansas License No.

Operation Completed: Hour 11:45 A Day 8 Month 12 Year 1973

The above well was plugged as follows:

RTD 3870' 8 5/8 csg set at 211' owe 150 sk.
Gunned pits, circulated heavy mud, set cementing plug at 975' and displaced 110 cu ft
cem thru drill pipe. Heavy mud to 215' set cementing plug and displaced 30 cu ft cem
thru drill pipe. Heavy mud to 200' set cementing plug, 1/2 sk hulls and 10 cu ft cem to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Len F. Mearns
Well Plugging Supervisor

DATE 12/10/73

INV. NO. 8274-W