

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 26 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 11-26-1968

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

15-065-20175-00-00

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name Donald C. Slawson

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Frigon Well No. A-1

Location: SE-SW-SW Sec. 33 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3976 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Clark was instructed to plug the well as follows:

241'--8 5/8" Surface casing, cement circulated with 200 Sx.  
3975'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3909'.

Sand well back to 3900' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 50 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

A. D. Nichols  
 Conservation Division Agent