



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

15-065-20657-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1974  
09-10-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center, Wichita, Kansas.

Lease Name: Hocker Well No. 1

Location: NE-NE-SE Sec. 34 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3880' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent