

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1967
06-26-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-065-20052-00-00

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Company has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Rice Estate Well No. B-1

Location: CNE-NW Sec. 31 Twp. 8 Rge. (E)(W) 22

County Graham Total Depth 3747' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

- 250' -- 8 5/8" Surface pipe, cement circulated with 165 Sx.
- Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.
- " " 270' and 25 Sx. cement.
- " " 40' with 1/2 sack hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent