



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-2 0165-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
08-19-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name: DeBoer Well No. 1

Location: CS/2-SW-NE Sec. 36 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3610 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 705'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent