

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20186-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 12-11-68

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Drig. Co. Inc., has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: 3 G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name: DeBoer Well No. 2

Location: NE-SE-NW Sec. 36 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3600 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP,
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent