



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20513-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas
01-10-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Kedco Corp., National Oil Co. and B & B Drlg., Inc.,

Complete Address: 816 Union Center, Wichita, Kansas.

Lease Name: Buss Well No. 1

Location: SE-SW-NW Sec. 36 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3620' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 110 Cu. Ft. cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent