

State of Kansas



15-065-20214-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Cotten of H-30 Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Cotten guarantees payment of the plugging fee.

Operator's full Name: H-30 Drilling, Incorporated

Complete Address: 200 North Main, Wichita, Kansas

Lease Name: Jones Well No. 1

Location: SW-SW-NE Sec. 10 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3955 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cotten was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

APR 25 1969

Very truly yours,

CONSERVATION DIVISION
 Wichita, Kansas

4-25-59

H. L. Nichols
 Conservation Division Agent