

State of Kansas



15-065-20133-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas
4-1-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Leo Lindenmuth of Chief Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated.

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Hull Well No. 1

Location: 150' West of CSE-SE Sec. 15 Twp. 8 Rge. (E)(W) 23

County Graham Total Depth 3118 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

231'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 930' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent