



15-065-30304-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this

date requested permission to plug the following described well:
Okmar Oil Co.

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Jones Well No. 1

Location: CNW-SW Sec. 15 Twp. 8 Rge. (E)(W) 23

County Graham Total Depth 3660 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

223' -- 8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210' with 1/4 sk. hulls &
		20 Sx. cement.
"	"	40' with 1/2 sk. hulls &
		10 Sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC -2 1965
12-2-65
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. L. Nichols
Conservation Division Agent