



15-065-20519-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1972
CONSERVATION DIVISION
Wichita, Kansas

10/2/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Incorporated,

Complete Address: 500 Bitting Building, Wichita, Kansas.

Lease Name: Keith Well No. 2

Location: CW/2-NE Sec. 16 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3725' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 185 Sx.
3724'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3690'. Only perforations shown from 3557' to 3567'.

Sand well back to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent