

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
~~J. P. Roberts~~
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-19152-00-01

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-70

Operator's Full Name Messman - Rinehart Oil Company
Complete Address: 1432 Wichita Plaza Wichita, Kansas
Lease Name Berland (OWWO) Well No. 1
Location NE NE SE Sec. 28 Twp. 8 Rge. (E) (W) 20
County Rooks Total Depth 3604'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: (OWWO)
Plugging Contractor: Murfin Drlg.
Address: Wichita, Kansas License No.
Operation Completed: Hour 2 P Day 28 Month 11 Year 1970

The Above well was plugged as follows:

RTD 3604' 13" csg set at 353' cwc Cmt. Mat. reg poz 6%.
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 50 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/1/70
INV. NO. 2954-W

Signed: Leo J. Murray
Well Plugging Supervisor