

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-20346-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1970
CONSERVATION DIVISION
Wichita, Kansas
7-9-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing
Complete Address 117 Cameron Bldg., ^{Oklahoma City,} Tulsa, Oklahoma
Lease Name Brin Well No. 1
Location NW NE SW Sec. 22 Twp: 8 Rge. (E) (W) 21
County Graham Total Depth 3653
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Aspen Drlg
Address Wichita, Kansas License No.
Operation Completed: Hour 9:30 A Day 8 Month 7 Year 1970

The above well was plugged as follows:

RTD 3653' 8 5/8 csg set at 218' cwc Cmt. Mat. 100 sk reg poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/9/70
INV. NO. 2193-W

Signed: Leo L. Massey
Well Plugging Supervisor