

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00137-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SE

SEC. 30 TWP. 8 RGE. 21W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Newell

Operator Nadel & Gussman Address Wichita, Kans

Field _____ County Graham

Total Depth 3752 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 5 1/2" at 3742'

Lane-Wells plugs at 3390', top perforations at 3360',

Filled with sand and chat to 3350', run 4csax cement with dump

bailer, pulled 3228' of 5 1/2", filled hold with rotary mud

to 170' set 10' rock bridge and 15 sax cement, filled with

mud to 35', set rock bridge and 10 sax cement to bottom

cellar.

5-25-50

PLUGGING
FILE SEC 30 T 8 R 21W
BOOK PAGE 7 LINE 41

J. Edson
District Conservation Agent
MAY 25 1950
5-24-50

Date _____