

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20481-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1971  
CONSERVATION DIVISION  
Wichita, Kansas

8-30-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Kirkpatrick Well No. 1

Location SE-NE-NE Sec. 31 Twp. 8 Rge. (E) (W) 21

County Graham Total Depth 3785'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:30 PM Day 25 Month 8 Year 1971

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru  
DP from 875' to 550'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from 215'  
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 8-31-71  
INV. NO. 4252-W