

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-005-20482-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1971
CONSERVATION DIVISION
Wichita, Kansas
9-2-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Munfin Drilling Company,
Complete Address 617 Union Center, Wichita, Kansas.
Lease Name Irby Well No. 1
Location SW-NE-SW Sec. 31 Twp. 8 Rge. (E) (W) 21
County Graham Total Depth 3385'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:30 AM Day 30 Month 8 Year 1971

The above well was plugged as follows:

197'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 100 Sx. cement thru
DP from 825' to 500'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from 215'
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE *9-2-71*
INV. NO. *4291-W*