



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1974
Sep 23, 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. Copeland Landes,
Complete Address 416 Union Center, Wichita, Kansas.
Lease Name Fountain Well No. 1
Location CW/2-SE-NW Sec. 33 Twp. 8 Rge. (E) (W) 21
County Graham Total Depth 3734'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Allied Cementing Company, Incorporated,
Address P. O. Box #31, Russell, Kansas. License No.
Operation Completed: Hour 10:30 AM Day 19 Month 9 Year 1974

The above well was plugged as follows:

250'--8 5/8" Surface casing cement circulated with 175 Sx.
3729'--4 1/2" Production casing cemented with 150 Sx. No plug-back, open hole comple-
tion. 2-Stage Collar set @ 1675' and cement circulated to surface with 450 Sx.
Squeezed 4 1/2" casing initially with 25 Cu. Ft. cement followed with 18 sacks gel to
1200' then 110 Cu. Ft. cement from 1200' to bottom of cellar. Maximum pump-in press-
ure-500#. FSIP-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Fichels
Well Plugging Supervisor

INVOICED

DATE 9/23/74
INV. NO. 9932-W