

15-065-21027-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 32 Twp. 8S Rge. 22W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE NW NE

Lease Owner Tomlinson Oil Company
Lease Name B. M. Korb Well No. 1-32
Office Address 200 W. Douglas, Suite 1030, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed Feb. 26 19 79
Application for plugging filed (verbally) Feb. 26 19 79
Application for plugging approved (verbally) Feb. 26 19 79
Plugging commenced Feb. 26 19 79
Plugging completed Feb. 26 19 79

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3868'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3868'
Set 1st plug at 800' with 70 sacks
2nd plug at 200' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks
Cemented with 50/50 posmix, 6% gel.
Plug was down at 1:30 p.m., 2-26-79.

RECEIVED
STATE CORPORATION COMMISSION
03-07-1979
MAR 7 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.



(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 79

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: 15-065-21027-00-00 B. M. Korb #1-32
 LOCATION: C NE NW NE, Section 32-8S-22W
 Graham County, Kansas
 SPUD DATE: February 18, 1979
 COMPLETION DATE: February 26, 1979

0	227	Sand and shale
227	520	Shale
520	1805	Sand and shale
1805	2190	Anhydrite and shale
2190	2665	Shale
2665	2865	Shale and lime
2865	3028	Shale
3028	3560	Lime and shale
3560	3648	Lime
3648	3680	Lime and shale
3680	3702	Lime
3702	3868	Lime and shale
	3868	Rotary Total Depth

Spud hole at 12:45 p.m., February 18, 1979. Drilled 227' of 12 1/4" hole. Ran 6 joints of 8-5/8" casing. Set at 225.51' K.B. with 175 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 5:30 p.m., February 18, 1979.

T.D. 3868'. Set 1st plug at 800' with 70 sacks, 2nd plug at 200' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 1:30 p.m., February 26, 1979.

SAMPLE TOPS:

Anhydrite 1811'
 B/Anhydrite 1847'

RECEIVED
 STATE CORPORATION COMMISSION
 MAR - 7 1979
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the B. M. Korb #1-32, C NE NW NE, Section 32-8S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 5th day of March, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.