

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-00367-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County, Sec. 33 Twp. 8 Rge. 22 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE

Lease Owner Harry Gore & Veeder Supply Company

Lease Name Desaire Well No. 1

Office Address 400 Brown Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-26 19 52

Application for plugging filed 10-26 19 52

Application for plugging approved 10-26 19 52

Plugging commenced 8:00 A. M. 10-26 19 52

Plugging completed 4:00 P. M. 10-26 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Hayes, Kansas

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 391 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled with mud to 190 feet.
Plug @ 190 ft 1/2 sack hulls and 15 sacks cement
Filled with mud to 40 feet.
Plug @ 40 feet 1/2 sack hulls and 15 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply & Development Company
Address Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Floyd Hild (employee of owner) or ~~representative~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) VEEDER SUPPLY & DEVELOPMENT CO.

BY: Floyd H. Hild (Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 19 52


Clerk Lawson Notary Public.

My commission expires July 11, 1956

PLUGGING
FILE SEC. 33 T. 8 R. 22
BOOK PAGE 55 LINE 23

15-065-00367-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm Desaire No. 1 Depth 3911
 Contractor Veeder Supply & Development Co. Pipe Set 200' of 8 5/8" casing
Cemented with 125 sacks cement
 Location Northwest Quarter Northwest Quarter Southeast Quarter Sec. 33 Twp. 8 Range 22
 Commenced 10-15-52 Completed 10-26-52 County Graham State Kansas

Sand Shale	0	130	130	Tops:	
Shale	130	850	720	Topoka	3270
Sand Shale Streaks	850	965	115	Heetner	3487
Shale	965	1300	335	Toronto	3513
Sand	1300	1555	255	Lansing KC	3526
Shale Shells	1555	1560	5	Base KC	3749
Shale	1560	1790	230	Conglomerate	3885
Anhydrite	1790	1828	38	Weathered Arbuckle	3891
Shale Shells	1828	2290	462	Solid Arbuckle	3898
Shale Shells Lime	2290	2450	160		
Lime Shale	2450	2490	40		
Lime	2490	2555	65		
Lime Shale	2555	2615	90	Plugged @ 190' with 15 sacks cement	
Shale Lime Shells	2615	2690	45	Plugged @ 40' with 10 sacks cement	
Lime Shale	2690	3269	579		
Lime	3269	3420	151		
Lime Shale	3420	3510	90		
Lime	3510	3890	380		
Shale	3890	3900	10		
Lime	3900	3911	11		

AFFIDAVIT

State of Kansas)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state that the above drilling log covering the Desaire #1 Well in Section 33, Township 8, Range 22, Graham County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

BY Floyd W. Hild

Subscribed and sworn to before me this 30th day of October, 1952.

Chas. Lawson
 Notary Public

My commission expires July 11, 1956.

PLUGGING
 FILE SEC. 33 T. 8 R. 22
 BOOK PAGE 537 VOL 23