


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec 33 Twp. 8S Rge. 22W(E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Frigon Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed August 11 1958
Application for plugging filed April 8 1960
Application for plugging approved April 14 1960
Plugging commenced April 15 1960
Plugging completed April 15 1960
Reason for abandonment of well or producing formation Commercial quantities of oil depleted.
If a producing well is abandoned, date of last production April 14 1960
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3883 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved on location, raised mast, checked hole
Sanded back to 3600' mixed and run 5 sacks
cement with dump bailer. Cleaned out cellar.
Took tension on pipe.
Loaded hole with water, worked pipe tension
to 25" shot casing at 2909' and worked until
free, pulled 52 jts.
Pulled 37 jts for total of 89 jts. Bailed
down fluid and mudded hole to 215' set 10'
rock bridge, mixed and run 5 sacks cement
mud to 40' set 10' rock bridge with 10 sacks
cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
05-03-1960
MAY 3 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. J. Boone (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: K. J. Boone Pet. Engr
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1960.

My commission expires July 7, 1962

Wesley L. Latimer
Notary Public.



R
DRILLER'S LOG

15-DUS-00616-00-00

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Frigon No. 1
SW SW SW Sec. 33-8S-22W
Graham County, Kansas

Total Depth: 3883'

Elevation: 2290' RB
Production: State Potential:
P 145 BOPD - 26% Wtr.
Grav. 30°

Commenced: 7-31-58 Completed: 8-11-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 215' with 150 sacks cement.
Set 5-1/2" Production Pipe at 3882' with 125 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Sand	215'		
Shale & Sand	1395'	Heebner	3498' (-1208)
Dakota Sand	1610'	Toronto	3521' (-1231)
Shale & Red Beds	1869'	Lansing	3533' (-1243)
Anhydrite	1904'	Arbuckle	3880' (-1590)
Shells & Shale	2235'	Rotary Total Depth	3883' (-1593)
Shale & Lime	3544'		
Lime	3883'		
Total Depth	3883'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *Harold L. Bacon*
Vice-President

Subscribed and sworn to before me this 2nd day of September, 1958.

My Commission Expires:

July 7, 1962

RECEIVED
STATE CORPORATION COMMISSION

Mona L. Latier
Notary Public

MAY 3 1960

CONSERVATION DIVISION
Wichita, Kansas