


15-065-00920-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 35 Twp. 8 Rge. 22 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NW/4 NW/4 SE/4
Lease Owner Veeder Supply & Dev'l. Co. et al
Lease Name Buss Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 4, 1956 19
Application for plugging filed Jan. 4, 1956 19
Application for plugging approved Jan. 4, 1956 19
Plugging commenced Jan. 4, 1956 19
Plugging completed Jan. 4, 1956 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 200' with 1/2 sack hulls, 15 sacks cement; mud to 40';
Set second plug at 40' with 1/2 sack hulls, 10 sacks cement,
cemented to bottom of cellar

RECEIVED
JAN 7 - 1956
DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Leo C. Veeder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder

Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1956

Loles Lawson
Notary Public.

My commission expires July 11, 1956

PLUGGING
FILE SEC 35 T 8 R 22W
BOOK PAGE 30 LINE 9

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Prugh Petroleum Company, Allan L. Melhado
 Drilled for Veeder Supply & Dev'l. Co. et al Farm Buss No. 1 Depth 3840
 Contractor Veeder supply & Dev'l. Co. Pipe 205' 8 5/8" csg. cemented w/140 sacks
 Location NW/4 NW/4 SE/4 Sec. 35 Twp. 8 Range 22
 Commenced 12-19-1955 Completed 1-11-1956 County Graham State Kansas

Cellar	0	9	9	TOPS:	
Sand, shale	9	60	51	Heebner	3351
Gray shale	60	120	60	K. C.	3396
Blue shale	120	350	230	Arbuckle	3791
Shale, shells	350	830	480		
Shale, shells, sand	830	1215	385		
Sand	1215	1435	220		
Shale and shells	1435	1535	100		
Shale, red bed	1535	1694	159		
Anhydrite	1694	1726	32		
Shale, shells	1726	2205	479		
Shells, shale, streaks					
Lime	2205	2390	185		
Lime and shale	2390	3275	885		
Lime	3275	3446	171		
Cherty lime	3446	3465	19		
Lime	3465	3840	375		
T. D.	3840				

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Buss #1 well located in Section 35-8-22, Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By: Leo C. Veeder.
Leo C. Veeder

Subscribed and sworn to before me this 6th day of January, 1956.

John Larson
Notary Public

My commission expires July 11, 1956.

RECEIVED
STATE COMMISSION
JAN 7 - 1956

PLUGGING
FILE SEC 35 T 8 R 22W
BOOK PAGE 30 LINE 9