

15-065-00107-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Graham County. Sec. 36 Twp. 8 Rge 22 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW NW NE

Lease Owner. W. A. Johnson

Lease Name. De Boer Well No. 1

Office Address.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed. June 15, 1949 19

Application for plugging filed. July 16, 1949 19

Application for plugging approved. July 27, 1949 19

Plugging commenced. July 17, 1949 19

Plugging completed. July 24, 1949 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes - first by telephone

Name of Conservation Agent who supervised plugging of this well. C. D. Stough, Great Bend, Kansas

Producing formation. Depth to top. Bottom. Total Depth of Well. Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

cemented with 6 sacks of cement from 3720 to 3690 feet

mud from 3690 feet to 270 feet

rock bridge from 270 feet to 255 feet

15 sacks of cement from 255 feet to 220 feet

mud from 220 feet to 30 feet

10 sacks of cement cap.

RECEIVED
08-01-1949
AUG 1 - 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. J. W. Braden Drilling Company

Address. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

J. W. Braden, partner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Braden

Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1949

M. L. Bowman

My commission expires March 21, 1953

Notary Public.

PLUGGING
FILE SEC 36 T 8 R 224
BOOK PAGE 166 LINE 45

DE BOREN #1
NW 1/4 of 36-8-22 Graham County, Kansas
Drilling Contractor - Braden Drilling Company
Operator - W. A. Johnson
Test Started - June 1, 1949
Test Completed - June 15, 1949

#####

Cellar	8
Clay & Sand	75
Shale & Shells	317
Shale	435
Shale & Shells	1135
Shale	1180
Sand	1405
Shale & Shells	1655
Anhydrite	1705
Shale & Lime	1760
Shale & Shells	1940
Shale & Red Rock	2050
Shale	2290
Shale & Lime	3210
Lime	4605
Shale	3620
Lime & Shale	3661
Shale	3692
Lime	3732

PIPE RECORD

317' of 8-5/8
3723' of 5 1/2" - cemented 100 sacks

Topped the Arbuckle Lime at 3722
and drilled to 3730 derrick floor.

STATE OF KANSAS)
) SS
COUNTY OF RENO)

I hereby certify that the above is correct and true
information as to the best of my knowledge.

J. M. Braden

Subscribed and sworn to before me, a Notary Public, this 16th day
of June, 1949.

M. L. Bowman
Notary Public

My Commission expires: March 21, 1953

PLUGGING
FILE SEC 26 8 22W
BOOK PAGE 106 LINE 45