

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-00972-00-00


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Graham County. Sec. 36 Twp. 8S Rge. 22 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Herndon Drilling Company  
Lease Name W. Van Loenen Estate Well No. 1  
Office Address Drawer 489, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-29-19 57  
Application for plugging filed 6-29-19 57  
Application for plugging approved 6-29-19 57  
Plugging commenced 6-29-19 57  
Plugging completed 6-29-19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3760 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 210 feet to 35 feet for each plug set.

Hole was filled to 210' w/rotary mud. 1/2 Sk. hulls was poured in to bridge plug. 20 Sx. Cement was mixed and poured in drill pipe. Hole was filled to 35', plug bridged w/1/2 sk. hulls and 10 sx. cement was mixed and poured in hole to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Herndon Drilling Company  
Address Drawer 489, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.  
Tom Elliott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elliott  
Drawer 489, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 57

My commission expires January 27, 1960 Judy Kiefer Notary Public.

PLUGGING  
FILE SEC 36 T 8 R 22W  
BOOK PAGE 24 LINE 41

15065-00972-00-00

WELL LOG ON W. VAN LOENEN ESTATE #1

Spudding date: 6/21/57  
Date casing set: 6/21/57  
Date rotary completed: 6/29/57  
Date cable completed:

Location:

NE SE NW, Section 36-8S-22W, Graham County, Kansas

FROM	TO	FORMATION	REMARKS
0	250	Surface Hole	Ran 9 Jts. 8-5/8" 24# J-55 Casing, set at 250' and cemented w/200 Sx. Common Cement w/2% C.C.
250	1230	Shale	
1230	1650	Shale & Shells	
1650	1690	Anhydrite	
1690	1960	Shale & Shells	
1960	2045	Shale	
2045	2495	Shale & Shells	
2495	2720	Lime & Shale	
2720	2820	Shale & Shells	
2820	3455	Shale & Lime	
3455	3760	Lime	Plugged hole w/20 Sx. Cement @ 210' - filled hole to 35' and plugged w/10 Sx. Cement to bottom of cellar.
3760		Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1957  
CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me this 3rd  
day of July, 19 57.

I certify the above and foregoing to be a true and exact copy of the original driller's log on the W. Van Loenen Estate #1.

HERNDON DRILLING COMPANY

[Signature]  
Notary Public  
My commission expires: 1-27-60

By: [Signature]  
Title: Assistant Secretary

PLUGGING  
FILE SEC 36 T 8 R 22W  
BOOK PAGE 24 LINE 41