


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines G S/2 SW NE
County. Graham Sec. 36 Twp 8S Rge. XX 22 (W)
Lease Owner Three G Oil, Inc.
Lease Name DeBoer Well No. 1
Office Address 1101 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 17 19 68
Application for plugging filed Verbal Authority
Application for plugging approved Verbal Authority
Plugging commenced August 17 19 68
Plugging completed August 17 19 68
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,610 feet (rotary total depth) to 900 feet. Set bottom plug at 900 feet and cemented with 100 sacks cement by Sun Oilwell Cementing, Inc. pump truck. Filled hole with heavy rotary mud to 215 feet. Set plug at 215 feet and cemented with 20 sacks cement by Sun pump truck. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement by Sun pump truck, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1968
CONSERVATION DIVISION
Wichita, Kansas
08-21-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 68

My commission expires April 21, 1971
Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Three G Oil, Inc.


SEC. 36 T. 8S R. 22W
 LOC. C S/2 SW NE

FARM DeBoer NO. 1

15-065-20165-00-00 COUNTY Graham

TOTAL DEPTH 3,610'
 COMM. August 9, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COMP. August 17, 1968



CASING

20	10		
15	8-5/8"	245' cemented w/150 sx cement	ELEVATION 2,142 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil, Sand & Clay	245
Shale & Shells	950
Shale	1150
Sand	1274
Shale	1440
Shale & Red Bed	1643
Anhydrite	1675
Shale & Shells	2060
Lime & Shale	2333
Lime	2345
Lime & Shale	2790
Shale & Lime Streaks	2960
Shale & Lime	3100
Shale, Lime & Streaks of Chert	3240
Lime & Shale	3334
Lime	3610
Rotary Total Depth	3610

ELECTRIC LOG TOPS:

Anhydrite	1643	+ 499
Base Anhydrite	1674	+ 468
Heebner	3330	-1188
Toronto	3356	-1214
Lansing	3373	-1231
Base K.C.	3576	-1434
Log T.D.	3608	-1466
Rotary T.D.	3610	-1468

RECEIVED
 STATE CORPORATION COMMISSION
AUG 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th day of August, 1968.

Martha Hartpence

 Martha Hartpence Notary Public

My Commission Expires:

April 21, 1971