

15-065-20513-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Graham County, Sec. 36 Twp. 8S Rge. (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner K & E DRILLING, INC.
Lease Name Buss Well No. 1
Office Address 816 Union Center - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 1-7- 19 72
Application for plugging filed 1-7 19 72
Application for plugging approved 1-7 19 72
Plugging commenced 8:30 PM 1-7 19 72
Plugging completed 9:30 PM 1-7 19 72
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production none 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole		0	218	8 5/8	215	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 875 w/110 Cu ft. @ 250' w/30 Cu ft. @ 40' w/10 cu ft.
2 sx in rat hole by Globe.

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1972
CONSERVATION DIVISION
Wichita, Kansas
01-13-1972

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
720 Union Center - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12 th day of January, 19 72

May 31, 1974

Alma A. Neises
Alma A. Neises
Notary Public.

My commission expires _____

15-065-20513-00-00

B & B DRILLING, INC.
207 Petroleum Building
Wichita, Kansas 67202

720 UNION CENTER

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1972

CONSERVATION DIVISION
Wichita, Kansas

January 12, 1972

DRILLERS LOG

Re: #1 Buss
SE SW NW Section 36-8S-22W
Graham County, Kansas

OPERATOR: K & E Drilling, Inc.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: January 1, 1972
COMPLETED: January 7, 1972
TOTAL DEPTH: 3620'

Set 8 5/8" @ 215' w/145 sx

0	218	Surface Hole
218	450	Shale & Sand
450	1296	Shale & Sand
1296	1686	Shale & Sand
1686	1718	Anhydrite
1718	1850	Shale & Sand
1850	2180	Shale & Red Bed
2180	2620	Shale & Lime
2620	3170	Shale & Lime
3170	3295	Lime & Shale
3295	3435	Lime
3435	3549	Lime
3549	3620	Lime
3620		Total Depth

DST #1 3458 - 3482'
DST #2 3555 - 3601'

D & A

We certify the above and foregoing to be true and correct copy of the log on the #1 Buss, located in Graham County, Kansas.

Bill Kahar President

Alma A. Neises Notary Public
Subscribed and sworn to before me this 12th day of January, 1972. My commission expires May 31, 1974

