

15-065-20214-00-00

Form CP-4

27

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Graham County, Sec. 10 Twp. 8 Rge. (E) 23(W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner H-30, INC.

Lease Name Jones Well No. 1

Office Address 200 N. Main, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 22 1969

Application for plugging filed " " 19 " "

Application for plugging approved " " 19 " "


Plugging commenced " " 19 " "

Plugging completed " " 19 " "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Sand	Water	0	50			
Shale	Dry	50	160	8-5/8	209	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,955 feet (rotary total depth) to 1,040'. Set bottom plug at 1,040' and cemented with 100 sacks of cement. Filled hole with heavy rotary mud to 215 feet. Set plug at 215 feet and cemented with 20 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rathole. Cementing service performed by Halliburton Pump Truck through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor H-30, INC. Address 200 N. Main St., Wichita, Kansas 67202

4-29-69

STATE OF KANSAS COUNTY OF SEDGWICK, ss. Richard G. Smith

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard G. Smith
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1969

My commission expires April 21, 1971 Martha Hartpence Notary Public.

15-065-20214-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


9

COMPANY **H-30, INC.**
 FARM **Jones** NO. **1**

SEC. **10 T. 8SR. 23W**
 LOC. **SW SW NE**

TOTAL DEPTH **3,955**
 COMM. **4-14-69** COMP. **4-22-69**
 SHOT OR TREATED
 CONTRACTOR **H-30, INC.**
 ISSUED

COUNTY **Graham**
 KANSAS



CASING
 20 10
 15 8 -5/8" @ 209' with 150 sx cement
 12 6
 13 5

ELEVATION **2234 GL**
2239 KB
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

SAMPLE TOPS

Surface Clay & Sand	50	Anhydrite	1894
Shale	1180	Heebner	3471
Shale and Sand	1445	Toronto	3497
Sand	1650	Lansing	3513
Red Bed	1894	Base K.C.	3726
Anhydrite	1926	Marmaton	3823
Shale	2250	Conglomerate	3888
Lime and Shale	3471	Arbuckle	3908
Black Shale	3477	RTD	3955
Lime	3823		
Shale & Lime Stringers	3908		
Dolomite	3955		
Rotary Total Depth	3955		

RECEIVED
 STATE CORPORATION COMMISSION
APR 29 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

4-29-69

H-30, INC.

Richard G. Smith

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th day of April, 1969.

Martha Hartpence, Notary Public

My Commission Expires:

April 21, 1971