

15-065-21072-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County. Sec. 10 Twp. 8S Rge. 23W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
SW NE SW

Lease Owner The Maurice L. Brown Company  
Lease Name Jones "B" Well No. 1

Office Address 200 Sutton Place, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole

Date Well completed Nov 9 1978

Application for plugging filed (verbally) Nov 9 1978

Application for plugging approved (verbally) Nov 9 1978

Plugging commenced Nov 9 1978

Plugging completed Nov 9 1978

Reason for abandonment of well or producing formation \_\_\_\_\_

No commercial quantity of oil or gas encountered

If a producing well is abandoned, date of last production \_\_\_\_\_  
19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3715'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. 3715'

Set 1st plug at 950' with 70 sacks

2nd plug at 240' with 20 sacks

3rd plug at 40' solid bridge with 10 sacks

rathole with 2 sacks

Cemented with 50/50 posmix, 6% gel.

Plug was down at 4:00 a.m., 11-9-78.

State Plugger - Gilbert Balthazor.

(If additional description is necessary, use BACK of this sheet) 11-17-78

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 78



Sherrie L. Brooks

Sherrie L. Brooks

Notary Public.

My commission expires August 21, 1982

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Jones "B" #1  
 LOCATION: SW NE SW, Section 10-8S-23W  
 Graham County, Kansas  
 SPUD DATE: November 1, 1978  
 COMPLETION DATE: November 9, 1978

0	253	Surface clay & sand
253	1854	Shale and sand
1854	1886	Anhydrite
1886	2230	Sand & Shale
2230	2980	Shale
2980	3180	Shale & Lime
3180	3390	Lime & Shale
3390	3525	Shale & Lime
3525	3630	Lime & Shale
3630	3715	Lime
	3715	Rotary Total Depth

Spud hole at 4:00 p.m., November 1, 1978. Drilled 253' of 12-1/4" hole. Ran 7 joints of 8-5/8" casing. Set at 250.93' with 190 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 9:30 p.m., November 1, 1978.

T.D. 3715'. Set 1st plug at 950' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 2 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 4:00 a.m., November 9, 1978.

SAMPLE TOPS:

Anhydrite 1854'  
 B/Anhydrite 1886'

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )


~~11-17-78~~

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc does hereby state that the above and foregoing is a true and correct copy of the log of the Jones "B" #1, SW NE SW, Section 10-8S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 15th day of November, 1978.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.