


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 11 Twp. 8 Rge. 23W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NW
Lease Owner The Carl Todd Drilling Company, etal
Lease Name McVey Well No. 1
Office Address 404 KFH Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-6 19 56
Application for plugging filed 3-6 19 56
Application for plugging approved 3-6 19 56
Plugging commenced 3-6 19 56
Plugging completed 3-6 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3936 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 200', set plug with 1/2 sack hulls and 20 sacks cement through drill pipe; bridge hole at 40' with 1/2 sack hulls and 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor The Carl Todd Drilling Company
Address 404 KFH Building, Wichita, Kansas 3-17-56

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Carl Todd (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Carl Todd
404 KFH Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of March, 19 56

My commission expires December 14, 1957

Martha Gorges
Notary Public.

PLUGGING
FILE SEC 11-8-23W
BOOK PAGE 44 LINE 37



15-065-00918-00-00

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

#1 McVey
SW SW NW Sec. 11-8S-23W
Graham County, Kansas

COMMENCED: February 27, 1956
COMPLETED: March 6, 1956

ELEVATION: 2235 Kelly Bushing

CASING RECORD

0 - 295	Shale and shells
295 - 350	Sand and shale
350 - 850	Shale and shells
850 - 975	Sand and Red Bed
975 - 1105	Shale and shells
1105 - 1200	Sand and Pyrite
1200 - 1890	Red Bed and shale
1890 - 1925	Anhydrite
1925 - 2535	Shale and shells
2535 - 3030	Lime and shale
3030 - 3311	Lime and shale
3311 - 3380	Lime (sandy)
3380 - 3593	Lime
3593 - 3729	Lime
3729 - 3780	Shale and lime
3780 - 3880	Lime and shale
3880 - 3904	Cong.
3904 - 3936	Lime
3936	Rotary Total Depth

8-5/8" OD 28# casing set at 218'
cemented with 165 sacks cement
3 sacks CC

TOPS

Heebner	3468
Toronto	3495
Lansing	3511
Base KC	3723
Conglomerate	3886
Arbuckle	3901

Drill Stem Test 3658 - 95
Weak blow for 2 minutes, flushed
tool at end of 30 minutes, no help.
Open 1 hour, recovered 5' mud,
no shows. IF & FF zero, BHP 30#
in 15 minutes.

I hereby certify that the above is a true and correct log,
to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By: *Carl Todd*

3-17-56

