


15-065-00353-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County, Sec. 12 Twp. 8 Rge. 23 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW NE
Lease Owner Harry Gore
Lease Name Hill City Airport Well No. 1
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/25 19 52
Application for plugging filed 9/25 19 52
Application for plugging approved 9/25 19 52
Plugging commenced 8 A.M. 9/25 19 52
Plugging completed 4 P.M. 9/25 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3930 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 190 ft.
Plugged @ 190' - 15 sacks cement run through drill pipe
Filled with Mud to 40 ft.
Plugged at 40 ft. 10 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply & Development Co.
Address Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Floyd Hild (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd H. Hild
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30th day of September, 19 52.


My commission expires Nov. 1, 1952.

Leo L. Veeder
Notary Public.

PLUGGING BOOK
FILE SEC 12 T. 8 R. 23
PAGE 42 LINE 2

RECEIVED
CORPORATION COMMISSION
OCT - 3 1952
10-3-52
CONSERVATION DIVISION
Wichita, Kansas

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm Hill City No. 1 Depth 3930
 Contractor Veeder Supply & Development Co. Set 196' of 8 5/8" casing
 Pipe Cemented with 125 sacks cement
 Location Northwest Quarter Northwest Quarter Northeast Quarter Sec. 12 Twp. 8 Range 23
 Commenced 9-15-52 Completed 9-25-52 County Graham State Kansas

Clay					
Soil/Sand	0	75	75		
Gray Shale Shells	75	150	75	Tops:	
Blue Shale	150	825	675	Topeka	3235
Gray Shale	825	1050	225	Heebner	3440
Shale Shells	1050	1390	340	Toronto	3463
Sand	1390	1545	155	Lansing K. C.	3477
Sand Shale	1545	1570	25	Shaly Conglomerate	3842
Shale Shells	1570	1850	280	Cherty Conglomerate	3857
Anhydrite	1850	1890	40	Arbuckle	3894
Shale Shells	1890	2250	360		
Lime Shells Shale	2250	2570	320		
Lime Shale	2570	2805	235		
Shale Lime Shells	2805	2940	135		
Lime Shale	2940	3040	100		
Lime Shells Shale	3040	3135	95		
Shale Shells	3135	3250	115		
Shale Lime	3250	3430	180		
Lime	3430	3700	270		
Lime Shale	3700	3897	197		
Arb. Lime	3897	3930	33		

Plugged C 190' with 15 sacks cement
 Plugged C 40' with 10 sacks cement

AFFIDAVIT

STATE OF KANSAS) SS
 Montgomery County)

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath says:
 I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and
 on oath state that the above drilling log covering the Hill City #1 Well in Section
 12, Township 8, Range 23, Graham County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

BY Floyd W. Hild

Subscribed and sworn to before me this 27th day of September, 1952.

Colo. Lawson
 Notary Public

My commission expires July 11, 1956

PLUGGING
 FILE SEC. 12 T. 8 R. 23
 BOOK PAGE 49 LINE 2

LIVED
 REGISTRATION COMMISSION
 OCT - 3 1952
 CONSERVATION DIVISION
 Wichita, Kansas

10-3-52