


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 13 Twp. 8S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Peel-Hardman Oil Operators
Lease Name Worchester Estate Well No. 1
Office Address R. R. #3, Box 144B, Wichita 15, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 8-26 19 58
Application for plugging filed 8-26 19 58
Application for plugging approved 8-26 19 58
Plugging commenced 8-26 19 58
Plugging completed 8-26 19 58
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3615 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	157'	8 5/8"	157	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3615 to 601 1/2 - Heavy Rotary Mud
" 601 1/2 to 600 - Wooden Plug
" 600' to 518' - 20 sacks cement
" 518' to 151 1/2' - Heavy Rotary Mud
" 151 1/2' to 150' - Wooden Plug
" 150' to 88' - 20 sacks Cement
" 88' to 41 1/2' - Heavy Rotary Mud
" 41 1/2' to 40' - Wooden Plug
" 40' to 6' - 10 sacks Cement
" 6' to Surface - Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
William Herbert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William Herbert*
R. R. #3, Box 144B, Wichita 15, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this _____ day of September, 19 58

My commission expires March 4, 1962
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1958
CONSERVATION DIVISION
Wichita, Kansas
9-5-58

PLUGGING
FILE SEC 13 T 8 R 23W
BOOK PAGE 127 LINE 42

DRILLER'S LOG

Company: Peel-Hardman Oil Operators

SE SE SE
Sec. 13-8S-23W

Farm: Worchester Estate Well No. 1

County: Graham,
Kansas

Total Depth: 3615'

Elevation:

Comm: 8-19-58 Comp.: 8-26-58

Production: Dry

Contractor: Glenn W. Peel Drilling Co.

Casing: 8 5/8" @ 157' cem.

Figures Below Indicate Bottom of Formation

Sand w/Share streaks	0	70'
Shale		157
Shale and shells		775
Sand and Shale		1000
Shale and shells		1150
Sand and shells		1270
Shale		1300
Sand		1500
Red Bed and Shale		1760
Anhydrite		1795
Shale		2205
Lime		2580
Lime and Shale		2780
Lime		3615
Total Depth		3615

This is to certify that the above information is to the best of my knowledge true and correct.

GLENN W. PEEL DRILLING CO.

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN TO before me this 3rd day of September 1958.

My commission expires March 4, 1962.

Marion M. Herbert
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1958
CONSERVATION DIVISION
Wichita, Kansas

9-5-58

PLUGGING
FILE SEC 13 T 8 R 23W
BOOK PAGE 127 LINE 42