

8-7 4-020017

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22721-00-00
C SE NE /4 SEC. 08, 08 S, 23 W
3300 feet from S section line
660 feet from E section line

Operator license# 4767

Lease: Montgomery "A" Well # 2

Operator: Ritchie Exploration, Inc.

County: Graham

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 3745 feet ^{121.71}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 203 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Co. License# 30606

Address: 250 N. Water, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: Day: 7 Month: August Year: 1993

Plugging proposal received from: Lloyd Delette

Company: Murfin Drilling Co. Phone: 316-267-3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1920 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1100 feet with 100 sacks

3rd plug @ 250 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:15, Day: 7, Month: August, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 1.9 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2242 GL

I did[] / did not[X] observe the plugging.

Ken Kuhn
(agent)

INVOICED
DATE 8-24-93
INV. NO. 38409

Form CP-223
RECEIVED
STATE CORPORATION COMMISSION
8-13-1993
AUG 13 1993