

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22812-00-00  
Spot: S2NESE Sec/Twnshp/Rge: 23-8S-23W  
1680 feet from S Section Line, 960 feet from E Section Line  
Lease/Unit Name: RIGGS Well Number: 1  
County: GRAHAM Total Vertical Depth: 3840 feet

Operator License No.: 30076  
Op Name: A & A PRODUCTION  
Address: PO BOX 100  
HILL CITY, KS 67642

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 205  
Production: Size feet:  
Liner: Size feet:

\$124.80

Well Type: DH UIC Docket No: Date/Time to Plug: 01/20/2001 12:30 PM

Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION

Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 01/20/2001 3:30 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1800' w/25 sxs. Anhydrite 1762' - 1802'.  
2nd. Plug at 1000' w/100 sxs. Dakota 683' - 983'.  
3rd. Plug at 260' w/40 sxs. Surface pipe at 205'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

INVOICED

DATE 3-06-2001

WELL NO. 2001061394

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 25 2001

1/25/01

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed



(TECHNICIAN)