

6 030696

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,850-00-00
300' N & 100' W
NE-SE-NE, SEC. 17, T. 8 S, R. 23 (W)P

3930' feet from S section line
430' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name BETHELL Well # 1

Operator: MID-CONTINENT ENERGY CORP. County GRAHAM 119.11

Name & Address 120 S. MARKET ST. 300 Well Total Depth 3665 feet

WICHITA, KANSAS Conductor Pipe: Size _____ feet

67202 Surface Casing: Size 8 5/8 feet 325'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING ^{ROSENKRANTS & BEMIS} License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 20 Month: 3 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 325 w/ 200 sx. 4 1/2 @ 3661 w/ 100 sx. PSTD 3624 PERF 3466-3564

ORDER SAND & COM. CMT. SHOOT & STRIP PIPE ORDER 350 SX. 60/4002

6066L 3 1/2 CC Allied cmt. Co. Water from creek.

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1986 4/7/86

Plugging Proposal Received by Carl Goodnow

(TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8: PM Day: 20 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PSTD TO 3400 SPOT 4 SX. COMCENT. ON

SAND W/BAILER. SHOT & STRIPPED 1502' of 4 1/2 COULDN'T PUMP DOWN

8 5/8 FOR TOP PLUG. ROSENKRANTZ & BEMIS PUSH & DRILL PLUG TO

1200' CIRCULATE 350 SX. THROUGH DRILL PIPE LAYDOWN 20 JOINTS

EACH STAGE & LOAD HOLE AFTER FINAL LAYDOWN. PLUG COMPLETE

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE APR 7 1986

Signed Carl Goodnow
(TECHNICIAN)

10
4-4-86

INV. NO. 13310 3-20 MAY 08 1986