

To: 6030510
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,568-00-00
NEUWUNE, SEC. 19, T. 8 S, R. 23 (W)
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6732

Lease Name Higer Well # 1

Operator: Vicorp Energy Inc.
Name & Address 62005 Syracuse way
Englewood CO.
80111

County Graham 122.50
Well Total Depth 3769 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 3/8 feet 227

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing License Number 6698

Address Box 108 Geneseo Ks. 67444

Company to plug at: Hour: PM Day: 10 Month: 7 Year: 19 85

Plugging proposal received from Nicholas

(company name) Nicholas Casing Pulling (phone) _____

were: 8 3/8 act @ 227' of 210' of 4 1/2 act @ 3767' of 150' of. Puffs
3679-83 Order sand - Com. cont. Shoot and pull pipe. PBTD 3703
Order 170' of 60/40 gel 3 1/2 cu 40' gel 3' shells.
Allied Cont. Co. Hedge water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 10 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Sand on PBTD to 3630 Dump 4' of cont w/ bailer
on sand. Recovered 1200' of 4 1/2 Top Plug pump down 8 3/8
of 2' shells + 32' gel. 100' of cont mix + 1' shells 8' gel. w.p.
50' of cont mix mat 450' Close in 150' Plug Complete.

STATE CORPORATION COMMISSION

7/19/85

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 7-24-85

Signed Carl Goodrow 7/18-85
(TECHNICIAN)

INV. NO. 9107