

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065- 21917-00-00

SW, Sec. 26, T 8 S, R 23 W
330 feet from W/S section line

330 feet from W/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5342

Lease Name Blackford Well # 1-26

Operator Name & Address Cherokee Petroleum
410 17th Suite 2300
DENVER COLO.
(303) 825-1966

County Graham

Well Total Depth 4073 feet 132.38

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well (D&A)

Other well as hereinafter indicated

Plugging Contractor Murfin Drilg. Co. License Number 6033

Address 250 No Water Wichita KS.

Company to plug at: Hour: AM Day: 26 Month: 3 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Lloyd Dallett

(company name) murfin Drilg. Co. (phone) 303 825-1966

were: order 210 sx. cement 50/50 pozmix 6% lye.

1sx hulls 1-8 5/8 plug 1sx. flow seal.

Heavy mud between all plugs

Pump cement down drill pipe.

Elev. 2307 Anhydrite 1763-97 Arbuckle - Yes

Dakota 1500 807 = 1100 Signed Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part (None)

Operations Completed: Hour: 12:30 PM Day: 26 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 4050 for 45 mi.

25 sx @ 4050

25 sx @ 1770

100 sx @ 1100 mixed with 1sx. flow seal

40 sx @ 300, 1sx hulls pushed plug to 40'

10 sx @ 40

10 sx in Rat Hole.

Remarks:

Hill city - 1-5 1-w 5 to dead end. 3/4 w 1-5
cementing w. Halliburton.

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

Signed Dale F. Balthazor (TECHNICIAN)

APR 02 1984 4-20-84

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 9-82 14

INVOICED

DATE 4-3-84

VV. NO. 115

APR 24 1984