

4-032330

11-18

API No. 15-065-02742-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1954

NW SE SW /4 SEC. 03, 08, 24 W
990 feet from S section line
3630 feet from E section line

Operator license# 100

Lease: Goff Well # 3

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990047-001

County: Graham 121.88
Well total depth 3750 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 119 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Poe Services License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 18 Month: November Year: 1998

Plugging proposal received from: Kansas Corporation Commission- Dist. #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order pulling unit.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 1 - 1998
12/1/98

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:50 A.M., Day: 18 Month: November, Year: 1998

Actual plugging report: 8 5/8" set at 119' cwc. 4 1/2" set at 3749' w/NA.
Prod. Perfs 3691' - 3697'. The well is sanded back to 1700' with junk in the hole. The last operator could not get down so ran in 1600' of tubing and rods with pump to draw oil off top of fluid, then abandoned the well. Holes in casing 1700' to 1150'. Squeezed 4 1/2" with 100 sxs cement blend with 350# hulls to Max. P.S.I. 1500#. S.I.P. 500#. Squeezed 8 5/8" with 50 sxs cement blend with 50# hulls mixed in to Max. P.S.I. 100#. S.I.P. 100#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)