

4-060585

9-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,746 -00-00

SE NW NW /4 SEC. 05, 08 S, 24 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5399 Lease Teel well # 1

Operator: American Energies Corporation County Graham

Address: 155 North Market - #710 Well total depth 3910 feet ^{127.07}
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mallard JV., Inc. License# 4958

Address: P.O. Box 1009 - McPherson, Kansas 67460

Company to plug at: Hour: 2:00P.M Day: 23 Month: September Year: 94

Plugging proposal received from: _____

Company: Mallard JV., Inc. Phone: 316-241-4640

Were: Order 200 sxs. 60/40 posmix - 6% gel with 1/4# flocele per. sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00P.M, Day: 23, Month: September, Year: 94

Actual plugging report: 8 5/8" to 255'.
1st. plug at 2100' w/25 sxs. - Anhydrite 2087' - 2121'.
2nd. plug at 1275' w/100 sxs. - Dakota 970' - 1270'.
3rd. plug at 305' w/40 sxs. - Surface pipe to 255'.
4th. plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2420 GL

I did[] or did not[] observe the plugging.

INVOICED

DATE OCT 06 1994
INV. NO. 41312

Received:
10-12-1994

Herb Deines

OH (agent)