

031129

7-7

15-065-02655-00-00

6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1958

NW NW NW, SEC. 4, T 8 S, R 24 W/E

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Nana NW Well # Unit 402

Operator: Oxy USA Inc.

County Graham 126.43

Name & Address 3545 NW 58th St.

Well Total Depth 3890 feet

Oklahoma City, OK. 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well x Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 7 Month: July Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 227' w/150 sks cwc 5 1/2" set at 3828' w/125 sks. PBDT

3826'. Perf 3792' - 3825'. Perfs at 2100' Anhy 1200' Base Dakota.

Order 300 sks Cement Blend w/600# Hulls. Allied Cement Co. Wellbrock

LaRue Hensley Water Trucks.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Hour 9:00AM Day: 7 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/300 sks cement w/500# Hulls to

max psi 750#. Close in 200#. Squeeze 8 5/8" w/50 sks cement w/100# Hulls

to max psi 500#. Close in psi 200#. Plug complete.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED
I () do hereby certify to serve this plugging.

DATE 10-25-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22708

Carl Goodrow

FORM CP-2/3 Rev. 01-84

RECEIVED
STATE CORPORATION COMMISSION
10-21-1988
OCT 21 1988
CONSERVATION DIVISION
Wichita, Kansas

D